



8 7 6 5 4 3 2 1

REVISIONS

REV.	DESCRIPTION	DATE	INIT
0	INITIAL RELEASE	10/17/14	MJS



- NOTES**
- 1) INITIAL VOLTAGE DROP MEASURED ACROSS TERMINALS IS 100mV MAX AT 3 AMPS WITH 12-15 VDC APPLIED
 - 2) SWITCH CIRCUIT WHEN OPEN WILL WITHSTAND 500 VDC WITH A MAX OF 5mA LEAKAGE (100K OHMS MIN)
 - 3) THE SWITCH AND LEADS WILL WITHSTAND 10" Hg VACUUM WHEN SUBMERGED IN WATER PER DSI "SALT WATER TEST"
 - 4) SWITCH HOUSING AND PLUNGER ARE CONSTRUCTED OF UV STABILIZED ACETAL COPOLYMER WITH 12% GLASS COLOR: BLACK
 - 5) ELECTRICAL RATING: 3A@12-14VDC LIFE = 100,000 CYCLES RESISTIVE
 - 6) INTERPRET THIS DRAWING IN ACCORDANCE WITH ASME Y14.5-2009

PROPRIETARY & CONFIDENTIAL THE INFORMATION CONTAINED IN THIS DRAWING IS THE SOLE PROPERTY OF DELTA SYSTEMS. ANY REPRODUCTION IN PART OR AS A WHOLE WITHOUT THE WRITTEN PERMISSION OF DELTA SYSTEMS IS PROHIBITED.	UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES TOLERANCES ARE: .X± .1 .XX± .02 .XXX± .005 X°± 1°	DRAWN mschwenning	DATE 17-Oct-2014	<p>DELTA SYSTEMS 1734 FROST ROAD STREETSBORO, OHIO 44241 330-626-2811 WWW.DELTASYSTEMSINC.COM</p>
		CHECKED bkirkman	DATE 18-Dec-2014	
APPROVED ikirbawy	DATE 18-Jun-2015	PROJECTED VIEWS ARE 3RD ANGLE 		
DELTA SYSTEMS INC. DOES NOT ASSUME ANY LIABILITY ARISING OUT OF THE MISAPPLICATION OF ANY PRODUCT	COMPUTER GENERATED DRAWING - NO MANUAL CHANGES ALLOWED	MATERIAL N/A	FINISH N/A	TITLE Universal Switch N.C. Application
		DO NOT SCALE DRAWING	STATUS	SIZE B
				DWG. NO. 7081-31_APP
				SCALE NTS
				SHEET 1 OF 1
				PROJECT NO. EX0257
				REVISION 0

8 7 6 5 4 3 2 1